



**NOTES:**

1. FOR ACCESS AND AIR VALVE MANHOLES.
2. CONCRETE EXTENSION COLLARS, MANHOLE RINGS, AND 6-INCH VALVE BOXES SHALL BE FIELD MORTARED. MORTAR: 1 PART PORTLAND CEMENT TO 3 PARTS SAND CONFORMING TO ASTM C 35.

<b>D DENVER WATER</b>	
<b>TYPICAL CONCRETE MANHOLE INSTALLATION</b>	
Scale: <u>  NONE  </u>	Date: <u>  May 2018  </u>
Drawn: <u>  RLB  </u>	Ck: <u>  K ROSS  </u>
Approved: <u>  Steph C. Reem  </u>	Dr. <u>  127  </u> No. <u>  35  </u>