



KEY NOTES:

- ① CURB STOP
- ② TYPE "K" CU TUBING
- ③ 2" COPPERSETTER/METER YOKE
- ④ METER W/ENCODER REGISTER
- ⑤ 3" NIPPLE BTWN COPPERSETTER AND CHKV (IF REQD)
- ⑥ 1"x 18" BSP-40
- ⑦ MIP TO FLARE CPLG FROM INLET SIDE OF COPPERSETTER & OUTLET SIDE OF CHKV
- ⑧ BY-PASS W/ VALVE WILL BE 1" FOR 1 1/2" COPPERSETTERS & 1 1/2" OR 1 1/4" FOR 2" COPPERSETTERS
- ⑨ CHKV - NOT REQD WHERE A BFP ASSY IS INSTALLED. BUT MAY BE REQD IF DIST TO BFP ASSY IS MORE THAN 150' & ALLOWS EXCESSIVE WTR TO DR DURING METER MAINTENANCE
- ⑩ 90° ELB
- ⑪ STD ADJ SPRT
- ⑫ SIGNAL WIRE TO AMR/AMI DEVICE
- ⑬ FD

NOTES:

1. NEW INSIDE METER INSTALLATIONS ARE PERMITTED ONLY BY WRITTEN APPROVAL. EXISTING INSIDE METER INSTALLATIONS SHALL COMPLY WITH THIS DRAWING.
2. INSTALLATION SHALL ALLOW FOR ACCESS FROM PUBLIC RIGHT-OF-WAY OR EASEMENT TO METER AND VALVES, AND PROVIDE PROTECTION FROM FREEZING.
3. A FLOOR DRAIN SHALL BE PLACED WITHIN 10- FEET OF THE METER INSTALLATION IN THE SAME ROOM.
4. METER SUPPORT MAY BE EITHER CONCRETE OR STRUCTURAL CHANNEL ATTACHED TO WALL.
5. WALL PENETRATIONS SHALL BE GROUTED WITH CONCRETE.
6. USC FCCCHR APPROVED DOUBLE CHECK VALVE OR REDUCED PRESSURE PRINCIPLE BACKFLOW PREVENTION ASSEMBLY DETERMINED BY DEGREE OF HAZARD POSED BY INTERNAL PLUMBING USE.
7. REFER TO LOCAL CODES AND MANUFACTURER REQUIREMENTS FOR SPECIFIC INSTALLATION INSTRUCTIONS.

ERRATA 2

D DENVER WATER	
INSIDE SETTING FOR 1 1/2" & 2" METER & BYPASS WITH INSIDE BACKFLOW PREVENTION ASSEMBLY	
Scale: <u> NONE </u>	Date: <u> January 2020 </u>
Drawn: <u> RLB </u>	Ck: <u> K ROSS </u>
Approved: <u> <i>[Signature]</i> </u>	Dr. <u> 127 </u> No. <u> 35 </u>